







WOODEN STEPPED BLOCK - HV	WOODEN STEPPED BLOCK - LV
	
QTY-3	QTY-3
DRW/CT-2314/8-1	

AXIAL WOODEN SUPPORT

QTY-4
DRW/CT-2314/8-1

CORE CORNER STICK				
				
A	B	C	L	QTY
25	3	4	838	12

WOODEN ROUND STICKS		
		
ROD DIA.	LENGTH	QTY
8	840	12
10	840	0
12	840	0

NOTE: ABOVE GIVEN QUANTITIES ARE REQUIRED FOR SINGLE TRANSFORMER (3xWINDINGS).

GENERAL TOLERANCES UNLESS OTHERWISE SPECIFIED				
HOLE SIZE ±0.05 / HOLE C-C ±0.05 / OTHER LINIER DIMENSIONS ±1				
REVISION NO.	DATE	DRAWN	DESCRIPTION	APPROVED BY
	<div>LTL Transformers (Pvt) Ltd</div> <div>154/11, Railway Station Road, Angulana, Moratuwa, Sri Lanka</div>			
PROJECT: APS TANZANIA LIMITED				
TITLE : ASSEMBLY STAGE TIMBER				
800kVA 11kV/400V TRANSFORMER				
DESIGNED BY:	SCALE: NTS		UNITS: mm	SIZE: A4
REVIEWED BY:	DRAWN BY: PRASHANTH		DESIGN NO:	
APPROVED BY:	DRAWING NO: DRW/CT-2314/80-5			
	DATE: 2023/06/27		REV: 00	